

CAMBRIDGE

MODEL: 700-PAW-HD-40K PORTABLE AXLE WEIGHER



- 80,000 LB CAPACITY PER SET
- (6) 20,000 LB ENVIRONMENTALLY SEALED LOAD CELLS PER SCALE
- POLYCARBONATE NEMA IV JUNCTION BOX
- 4" STRUCTURAL TUBULAR STEEL CONSTRUCTION
- ¼" DIAMOND TREAD DECK PLATE
- 200% OVERLOAD PROTECTION
- CAPTIVE BALL LEVELING FEET
- TOP ACCESS LEVELING
- TOP ACCESS JUNCTION BOX

<u>MODEL</u>	<u>DESCRIPTION</u>	<u>SIZE</u>	<u>CAPACITY</u>	<u>WEIGHT</u>	<u>LIST EA.</u>
700-PAW-HD-40K	PORTABLE AXLE WEIGHER	32"x12'x6"	40,000 LB	1035#	\$5,695.
700-PAW-HD-40K	PORTABLE AXLE WEIGHER	32"x14'x6"	40,000 LB	1730#	\$6,695.
700-PAW-HD-LG-40K	LANDING GEAR SCALE	9'x3'x6"	40,000 LB	1000#	\$4,993.

OPTIONS

- Wi-Cell Wireless Load Cell Communication (from Axle Scale to Indicator)
- (6) 20K "FM" LOAD CELLS
- (6) 20K STAINLESS STEEL LOAD CELLS, HARDWARE, & LEVELING FEET

<u>LIST</u>
\$1,695.00
\$ 429.00
\$1,215.00

ACCESSORIES

700-PAW-HD RAMPS

<u>MODEL</u>	<u>DESCRIPTION</u>	<u>SIZE</u>	<u>CAPACITY</u>	<u>WEIGHT</u>	<u>LIST EA.</u>
700-PAW-HD	RAMP W/ASPHALT PACKAGE	32"x36"x6"	30K-40K	250#	\$570.00
700-PAW-HD	RAMP W/HARD PACK PACKAGE	32"x36"x6"	30K-40K	450#	\$995.00
700-PAW-HD-LG	RAMP W/ASPHALT PACKAGE	9'x3'x6"	30K-40K	675#	\$1200.00
700-PAW-HD	LEVEL SPACER MODULE	32"x5'x6"	30K-40K	575#	\$1070.00

<u>PART #:</u>	<u>DESCRIPTION</u>	<u>LIST (EA)</u>
*50152	ASPHALT/LOCATOR/LAG DOWN PLATE	\$140.00
*50153	ASPHALT/LOCATOR/LAG DOWN PLATE	\$140.00

* LAG DOWN PLATES REQUIRED WHEN NO RAMPS ARE USED OR 2 RAMPS ARE USED AT ONE END ONLY

*50168	ASPHALT/LOCATOR/LAG DOWN PLATE	\$279.00
--------	--------------------------------	----------

* LAG DOWN PLATES REQUIRED WHEN 2 OR MORE 700-PAW-HD SCALES ARE USED TOGETHER
(ie: MULTI-DECK SCALE SYSTEM)

PIT FRAMES

<u>MODEL</u>	<u>DESCRIPTION</u>	<u>SIZE</u>	<u>CAPACITY</u>	<u>WEIGHT</u>	<u>LIST EA.</u>
700-PAW-HD	PIT FRAME	32"x84"x6"	30K-40K	325#	\$650.00
700-PAW-HD	PIT FRAME	32"x120"x6"	30K-40K	450#	\$930.00

F.O.B. HONEY BROOK, PA

EFFECTIVE DATE: 1/01/17

PRICES SUBJECT TO CHANGE WITHOUT NOTICE